



CITY OF LODI

PUBLIC WORKS DEPARTMENT

COUNCIL COMMUNICATION

TO: City Council

FROM: City Manager

MEETING DATE: April 4, 1990

AGENDA TITLE: Contract Award and Appropriation of Funds for Lower Sacramento Road Improvements, 900 Feet South of Lodi Avenue to 400 Feet North of Tejon Street, and Removal of Stop Signs on Lower Sacramento Road at Park West Drive

Project Data
Total Project Estimate: \$278,000.00
Bid Opening Date: 4/4/90

This project consists of pavement widening and restriping along Lower Sacramento Road to provide left turn pockets at the major intersections and construction of traffic signals and street improvement at the intersection of Lower Sacramento Road and Elm Street, including extension of the frontage road to Elm Street.

Traffic backed up from the stop sign on Lower Sacramento Road at Park West Drive extends into the Elm Street intersection. This will interfere with the operation of the new signal at Elm Street. With the signal and the frontage road extension, the stop sign on Lower Sacramento Road is an unnecessary traffic control device.

The bid opening for this project is set for April 4, 1990, the date of the City Council meeting. Assuming there are no problems with the bids, an award recommendation will be made at the meeting.

Jack L. Ronsko
Public Works Director

JLR/RCP/mt

cc: Purchasing Officer
Street Superintendent

APPROVED:

THOMAS A. PETERSON, City Manager

FILE NO.



CITY OF LODI

PUBLIC WORKS DEPARTMENT

COUNCIL COMMUNICATION

TO: City Council Project Data

FROM: City Manager Bid Opening Date: 4/4/90

MEETING DATE: April 4, 1990

AGENDA TITLE: Contract Award and Appropriation of Funds for Lower Sacramento Road Improvements, 900 Feet South of Lodi Avenue to 400 Feet North of Tejon Street, and Removal of Stop Signs on Lower Sacramento Road at Park West Drive

RECOMMENDED ACTION: That the City Council award the contract for the above project to Claude C. Wood Company in the amount of \$340,974.40 with full depth asphalt concrete structural section (Alternate B) and Schedule 1, Median Curb and Gutter South of Elm Street, and authorize the City Manager to reappropriate funds for the project.

BACKGROUND INFORMATION: This project consists of pavement widening and restriping along Lower Sacramento Road to provide left turn pockets at the major intersections and construction of traffic signals and street improvement at the intersection of Lower Sacramento Road and Elm Street, including extension of the frontage road to Elm Street.

Traffic backed up from the stop sign on Lower Sacramento Road at Park West Drive extends into the Elm Street intersection. This will interfere with the operation of the new signal at Elm Street. With the signal and the frontage road extension, the stop sign on Lower Sacramento Road is an unnecessary traffic control device.

Plans and specifications for this project were approved on March 21, 1990.

The City received one bid for this project. A bid tabulation is attached.

Staff has reviewed the bid with Claude C. Wood Company and sees no reasonable way to substantially reduce the cost of the project. Other potential bidders were also contacted. Apparently the volume of work presently underway or being bid precluded receiving additional bids.

The total cost of the project and recommended funding is shown below.

Project Costs

Final Engineering & City-Furnished	
Signal Materials	\$ 30,000
Construction Contract	341,000
Contingencies & Construction Engineering	34,000
	<u>\$405,000</u>

APPROVED:

THOMAS A. PETERSON, City Manager

FILE NO.

City Council
Lower Sacramento Road Improvements
April 4, 1990
Page 2

Funding

Already Budgeted (non-FAU)	\$ 31,600	
Unappropriated TDA (124 Fund)	96,000	
Unappropriated Gas Tax (32 Fund)	17,800	
Church Street Overlay	67,600	(project was dropped in favor of reconstruction/widening)
Misc. Curb & Gutter (33 Fund)	14,600	
Misc. Widening (33 Fund)	21,200	
Lodi Avenue Overlay	142,000	(project is not ready; will rebudget next year)
Misc. Water, Wastewater & Storm	14,200	
	<u>\$405,000</u>	

Richard C. Ronsko

for Jack L. Ronsko
Public Works Director

JLR/RCP/mt

Attachment

cc: Purchasing Officer
Street Superintendent

City of Lodi - Public Work Department

Bid Tabulation

Project: Lower Sacramento Road Improvement

Bids Opened: April 4th, 1990

Engineer's Estimate

Claude C. Wood

Item	Description	Total Quantity	Unit	Unit Price	Total	Unit Price	Total
1	Clearing & Grubbing	1	LS	\$10,000.00	\$10,000.00	\$11,000.00	\$11,000.00
2	Compact Original Ground	83,225	SF	0.15	12,483.75	0.20	16645.00
3	Pavement Grinding (1.5')	3,564	LF	0.75	2,673.00	0.60	2138.40
4	Misc. Concrete Subgrade Comp.	2,750	SF	1.00	2,750.00	2.00	5500.00
5	Vertical Curb & Gutter	447	LF	15.00	6,705.00	12.00	5364.00
6	Median Curb	108	LF	13.00	1,404.00	10.00	1080.00
7	AC Curb	132	LF	8.00	1,056.00	10.00	1320.00
8	Sidewalk	1,522	SF	4.00	6,088.00	6.00	9132.00
9	Signs & Delineators	1	LS	1,500.00	1,500.00	6,500.00	6500.00
10	Traffic Signal Elm / Lwr Sac	1	LS	50,000.00	50,000.00	72,000.00	72000.00
11	Pavement Striping & Markers	1	LS	3,000.00	3,000.00	8,000.00	8000.00
12	Removal Of Striping & Markers	1	LS	7,500.00	7,500.00	8,500.00	8500.00
13	Traffic Control	1	LS	2,000.00	2,000.00	13,500.00	13500.00
14	Street Light	1	EA	2,000.00	2,000.00	1,600.00	1600.00
15	8" Water Main	80	LF	60.00	4,800.00	50.00	4000.00
16	Blow-Off	1	EA	200.00	200.00	550.00	550.00
17	Adjust Water Valve Frame & Cover	4	EA	300.00	1,200.00	400.00	1600.00
18	12" Storm Drain	29	LF	60.00	1,740.00	200.00	5800.00
19	Drop Inlet Catch Basin	1	EA	800.00	800.00	850.00	850.00
20	Abandon Drop Inlet Catch Basin	1	EA	200.00	200.00	500.00	500.00
21	Adjust Manhole Frame & Cover	4	EA	315.00	1,260.00	450.00	1800.00
22	Excavation Safety	1	LS	500.00	500.00	500.00	500.00
Base Bid Subtotal					\$119,859.75		\$177,879.10
Structure Section - Alternate A							
1	Roadway Excavation	4,014	CY	\$10.00	\$40,140.00	\$11.00	\$44,154.00
2	Aggregate Base	3,312	Ton	17.00	56,304.00	15.00	49,680.00
3	Asphalt Concrete	1,791	Ton	34.00	60,894.00	38.00	68,058.00
Alternate A Subtotal					\$157,338.00		\$161,892.00
Structural Section - Alternate B							
1	Roadway Excavation	3,113	CY	\$11.00	\$34,243.00	\$12.00	\$37,356.00
2	Asphalt Concrete	3,301	Ton	33.50	110,583.50	36.00	118,836.00
Alternate B Subtotal					\$144,826.50		\$156,192.00
Subtotal Base + Alternate A					\$277,197.75		\$339,771.40
*Lower Alternate Cost >>>>>> Subtotal Base + Alternate B					\$264,686.25		\$334,071.40
Schedule 1 - East Side Median (S/Elm)							
1	Vertical Curb & Gutter	341	LF	\$15.00	\$5,115.00	\$12.00	\$4,092.00
2	Misc. Concrete Subgrade Comp.	937	SF	1.00	937.00	3.00	2,811.00
Schedule 1 Subtotal					\$6,052.00		\$6,903.00
Base Subtotal + Lower Alternate + Schedule 1					\$270,738.25		\$340,974.40

EXHIBIT A

City of Lodi - Public Work Department

Bid Tabulation

Project: Lower Sacramento Road Improvement

Bids Opened: April 4th, 1990

Engineer's Estimate

Claude C. Wood

Item	Description	Total		Unit		Unit	
		Quantity	Unit	Price	Total	Price	Total
1	Clearing & Grubbing	1	LS	\$10,000.00	\$10,000.00	\$11,000.00	\$11,000.00
2	Compact Original Ground	83,225	SF	0.15	12,483.75	0.20	16645.00
3	Pavement Grinding (1.5')	3,564	LF	0.75	2,673.00	0.60	2138.40
4	Misc. Concrete Subgrade Comp.	2,750	SF	1.00	2,750.00	2.00	5500.00
5	Vertical Curb & Gutter	447	LF	15.00	6,705.00	12.00	5364.00
6	Median Curb	108	LF	13.00	1,404.00	10.00	1080.00
7	AC Curb	132	LF	8.00	1,056.00	10.00	1320.00
8	Sidewalk	1,522	SF	4.00	6,088.00	6.00	9132.00
9	Signs & Delineators	1	LS	1,500.00	1,500.00	6,500.00	6500.00
10	Traffic Signal Elm / Lwr Sac	1	LS	50,000.00	50,000.00	72,000.00	72000.00
11	Pavement Striping & Markers	1	LS	3,000.00	3,000.00	8,000.00	8000.00
12	Removal Of Striping & Markers	1	LS	7,500.00	7,500.00	8,500.00	8500.00
13	Traffic Control	1	LS	2,000.00	2,000.00	13,500.00	13500.00
14	Street Light	1	EA	2,000.00	2,000.00	1,600.00	1600.00
15	8" Water Main	80	LF	60.00	4,800.00	50.00	4000.00
16	Blow-Off	1	EA	200.00	200.00	550.00	550.00
17	Adjust Water Valve Frame & Cover	4	EA	300.00	1,200.00	400.00	1600.00
18	12' Storm Drain	29	LF	60.00	1,740.00	200.00	5800.00
19	Drop Inlet Catch Basin	1	EA	800.00	800.00	850.00	850.00
20	Abandon Drop Inlet Catch Basin	1	EA	200.00	200.00	500.00	500.00
21	Adjust Manhole Frame & Cover	4	EA	315.00	1,260.00	450.00	1800.00
22	Excavation Safety	1	LS	500.00	500.00	500.00	500.00
Base Bid Subtotal					\$119,859.75		\$177,879.40
Structure Section - Alternate A							
1	Roadway Excavation	4,014	CY	\$10.00	\$40,140.00	\$11.00	\$44,154.00
2	Aggregate Base	3,312	Ton	17.00	56,304.00	15.00	49680.00
3	Asphalt Concrete	1,791	Ton	34.00	60,894.00	38.00	68058.00
Alternate A Subtotal					\$157,338.00		\$161,892.00
Structural Section - Alternate B							
1	Roadway Excavation	3,113	CY	\$11.00	\$34,243.00	\$12.00	\$37,356.00
2	Asphalt Concrete	3,301	Ton	33.50	110,583.50	36.00	118836.00
Alternate B Subtotal					\$144,826.50		\$156,192.00
Subtotal Base + Alternate A					\$277,197.75		\$339,771.40
Subtotal Base + Alternate B					\$264,686.25		\$334,071.40
Schedule 1 - East Side Median (S/Elm)							
1	Vertical Curb & Gutter	341	LF	\$15.00	\$5,115.00	\$12.00	\$4,092.00
2	Misc. Concrete Subgrade Comp.	937	SF	1.00	937.00	3.00	2,811.00
Schedule 1 Subtotal					\$6,052.00		\$6,903.00
Base Subtotal + Lower Alternate + Schedule 1					\$270,738.25		\$340,974.40

4/4/90

RESOLUTION NO. 90-53
=====

A RESOLUTION OF THE LODI CITY COUNCIL
AWARDING THE CONTRACT AND APPROPRIATING FUNDS FOR LOWER SACRAMENTO ROAD
IMPROVEMENTS, 900 FEET SOUTH OF LODI AVENUE TO 400 FEET NORTH OF TEJON STREET,
AND REMOVAL OF STOP SIGNS ON LOWER SACRAMENTO ROAD AT PARK WEST DRIVE

=====

WHEREAS, in answer to notice duly published in accordance with law and the order of this City Council, sealed bids were received and publicly opened on April 4, 1990 at 11:00 a.m. for the contract for Lower Sacramento Road improvements, 900 feet south of Lodi Avenue to 400 feet north of Tejon Street, and removal of stop signs on Lower Sacramento Road at Park West Drive, described in the specifications therefor approved by the City Council on March 21, 1990; and

WHEREAS, only one bid was received for this project from Claude C. Wood Company, and said bid has been compared, checked, and tabulated and a report thereof filed with the City Manager as shown on Exhibit A attached hereto; and

WHEREAS, the City Manager recommends that award of the contract for Lower Sacramento Road improvements, 900 feet south of Lodi Avenue to 400 feet north of Tejon Street, and removal of stop signs on Lower Sacramento Road at Park West Drive be made to the sole bidder, Claude C. Wood Company for full depth asphalt concrete structural section (Alternate B) and Schedule 1, Median Curb and Gutter South of Elm Street;

NOW, THEREFORE, BE IT RESOLVED by the Lodi City Council that award of contract for Lower Sacramento Road improvements, 900 feet south of Lodi Avenue to 400 feet north of Tejon Street, and removal of stop signs on Lower Sacramento Road at Park West Drive be and the same is hereby awarded to the sole bidder, Claude C. Wood Company, for full depth asphalt concrete structural section (Alternate B) and Schedule 1, Median Curb and Gutter South of Elm Street, in the amount of \$340,974.40; and

BE IT FURTHER RESOLVED, that the City Council hereby authorizes the City Manager to reappropriate funds for the project.

Dated: April 4, 1990

=====

I hereby certify that Resolution No. 90-53 was passed and adopted by the City Council of the City of Lodi in a regular meeting held April 4, 1990 by the following vote:

- Ayes: Council Members - Hinchman, Olson, Pinkerton, Reid and Snider (Mayor)
- Noes: Council Members - None
- Absent: Council Members - None

Alice M. Reimche
Alice M. Reimche
City Clerk