



CITY OF LODI

PUBLIC WORKS DEPARTMENT

COUNCIL COMMUNICATION

TO :	City Council	Project Data for Construction Only	
		Budgeted Fund:	17.2-10.61
FROM :	City Manager	Amount Budgeted:	\$9,100,000
		Total Project Estimate:	\$8,800,000
MEETING DATE:	July 19, 1989	Bid Opening Date:	9/6/89
AGENDA TITLE:	Plans and Specifications for White Slough Water Pollution Control Facility Expansion Project, 12751 North Thornton Road		

RECOMMENDED ACTION: That the City Council approve the plans and specifications for the above project and authorize advertising for bids.

BACKGROUND INFORMATION: This project provides for the expansion of the White Slough Water Pollution Control Facility. Facilities to be constructed include new primary sedimentation basins, aeration basin, secondary clarifier complex, anaerobic digesters, and dissolved air flotation thickener; and modifications to chlorine contact tanks, chlorination facilities, headworks, sludge lagoons, control building, site work and yard piping. This will expand the design flow from 5.8 million gallons per day (MGD) to 8.5 MGD. the construction of this project will take approximately 1½ years.

Black & Veatch Engineers (B&V) of Walnut Creek has designed this expansion and has prepared the plans and specifications.


Jack L. Ronsko
Public Works Director

JLR/mt

cc: Purchasing Officer
Water/Wastewater Superintendent

APPROVED:


THOMAS A. PETERSON, City Manager

FILE NO.

CWSWPC10/TXTW.02M

July 12, 1989